



集装箱码头全自动化带来的新挑战

New Challenges Posed by Full Automation Of Container Terminal



IAPH Guangzhou 2019 World
Ports Conference

目录

CONTENTS

01

一、青岛港全自动化集装箱码头简介

Brief Introduction of Qingdao Port Fully Automated Container Terminal

02

二、集装箱码头全自动化带来的新挑战

New challenges Posed by Full Automation of Container Terminal

03

三、全自动化集装箱码头优化方向

The Optimization Direction of Fully Automated Container Terminal



青岛港全自动化集装箱码头简介

Brief Introduction of Qingdao Port Fully Automated Container Terminal

- 码头岸线总长2088米，水深-20米，规划建设6个泊位，设计年通过能力520万TEU，可靠泊24000TEU及以上船舶
- Quay length of 2088 meters, water depth of - 20 meters, planning to build six berths with the designed capacity of 5.2 million TEU, berthing 24,000 TEU ships



Qingdao Port Fully Automated Container Terminal

青岛港全自动化集装箱码头



青岛港全自动化集装箱码头简介

Brief Introduction of Qingdao Port Fully Automated Container Terminal

- 码头分三期建设，一期2013年10底启动，2017年5月投入商业运营，配备7台自动化桥吊，38台自动导引车，38台自动化高速轨道吊
- The first phase was started at the end of October 2013 and put into commercial operation in May 2017. It is equipped with 7 automatic quay cranes, 38 automatic guided vehicles and 38 automatic high-speed stacking cranes.



青岛港全自动化集装箱码头

Qingdao Port Fully Automated Container Terminal



全自动化集装箱码头的主要优势

Main advantages of fully automated container terminal

- 全自动化集装箱码头的主要优势
- Main advantages of fully automated container terminal
 - 节省人工 Labor Saving
 - 降低运营成本 Reduce Operating costs
 - 提高效率 Improve productivity
 - 安全可靠 Safe and reliable
 - 节能环保 Energy saving and Environmental

.....



集装箱码头全自动化带来的新挑战

New Challenges Posed by Full Automation Of Container Terminal

- 平面布局规划 Layout Planning

- AGV运行区设计 AGV area design
- 冷藏箱区设计 Reefer area design
- 外集卡倒车区域设计 Landside external truck reverse area design

- 土建设计 Civil Construction Design

- 地面承载力要求及施工工艺 Requirements of Ground bearing capacity(Standard) and Construction process
- 码头平面度要求 Standard of terminal surface flatness
- 码头不均匀沉降控制（标准、规范） How to control uneven sedimentation of terminal(Standard)
- 轨道平面度及安装施工工艺 ASC track flatness and installation & construction technique



集装箱码头全自动化带来的新挑战

New Challenges Posed by Full Automation Of Container Terminal

- 设备设计与制造 Equipment design and manufacturing
 - 制造精度要求 Manufacturing accuracy requirements
 - 制造刚度要求 Manufacturing stiffness requirements
 - 可靠性原则及标准 Principles and standards of reliability
 - 可维护性及免维护 Maintainability and maintenance-free
- IT系统开发与测试 IT system development & testing
 - 智能算法多，开发难度大 Intelligent algorithms development
 - 系统接口多，测试周期长 Many interfaces and long testing cycle
 - IT基础架构设计 IT infrastructure design
 - 工控网络安全 Industrial control network security



集装箱码头全自动化带来的新挑战

New Challenges Posed by Full Automation Of Container Terminal

- 自动化工艺流程设计 Automated Process Flow design
 - 自动化流程 Automation process
 - 堆场策略设计 Yard stacking strategy design
- 项目管理及人员配备 Project Management and staffing
 - 多家供应商协调管理 Coordination management of multiple suppliers
 - 人员技能水平 Skill Level of Personnel
- 安全管理 Safety Management
 - 设备无人化带来的新挑战 New Challenges Posed by Unmanned Equipment
 - 人体感知缺失 Absence of human perception
 - 漏摘集装箱扭锁 Missing of Container Twist Lock



集装箱码头全自动化带来的新挑战

New Challenges Posed by Full Automation Of Container Terminal

- 码头运营管理

- 人员岗位设置及其职能描述（与自动化生产流程及管理方式相适应）

- Personnel post setting and function description (adapted to automated production process and management mode)

- 人员配置及培训 Staffing and training

- 薪酬体系建立 Establishment of Compensation System

- 公司架构及部门设置 Corporate Structure and Departmental Settings

- 如何在船舶大型化的背景下实现更高的码头效率？

- How to achieve higher terminal efficiency under the background of large-scale ships?



如何在船舶大型化的背景下实现更高的码头效率?

How to achieve higher efficiency under the background of Megaships?

- 船舶大型化趋势 Trend of Mega Ships

- 超过2万标箱的大型集装箱船舶 Mega Ships with Over 20,000 TEU

- 对港口的装卸效率要求越来越高 Higher and Higher Requirements for Port Handling Efficiency



- 需开发高效自动化桥吊 Need to Develop High Efficiency Automatic Quay Crane



如何在船舶大型化的背景下实现更高的码头效率？

How to achieve higher efficiency under the background of Megaships?

- 青岛港自动化码头的桥吊结构及参数
- Quay Crane Structure and Parameters of Qingdao Port Automated Terminal



主小车承担船到平台的装卸作业
门架小车承担平台到AGV装卸作业

单起升双小车桥吊，起重量70吨，前伸距70米，起升高度50+22米，主起升速度90/180米/分钟，主小车速度240米/分钟。



高效自动化桥吊 High-efficiency automated STS

- 对吊具的有效控制是提升作业效率的最有效途径
Effective control of spreader is the most effective way to improve operation efficiency
 - 国外有轨道吊采用机械方式实现对吊具的刚性控制，但无法应用在桥吊上
Overseas ASC users use mechanical methods to achieve rigid control of spreaders, but can not be applied to QC





高效自动化桥吊 High-efficiency automated STS

- 拟采用大扭矩低速永磁电机替代现有的三相异步电机、减速箱和钢丝绳卷筒 It is proposed to replace the existing three-phase asynchronous motor, reducer and wire rope drum with large torque and low speed permanent magnet motor
- 将起升机构从机房移至主小车上，从而实现可分离八绳结构，最终实现对吊具的有效控制 The hoist mechanism is moved from the engine room to the main trolley, thus realizing the separable eight-rope structure, and ultimately realizing the effective control of the spreader.



高效自动化桥吊 High-efficiency automated STS

桥吊八绳吊具防摇系统 eight-rope anti-swing structure



实现对吊具的有效控制，防止摇动扭摆
Ultimately realizing the effective control of
the spreader and anti-swing



自动化集装箱码头的优化方向

The Optimization Direction of Fully Automated Container Terminal

- 提升自动化码头生产管理系统的智能化水平 Promoting the Intelligent Level of Terminal Operating Management System of Automated Terminal
- 运用5G技术实现堆场轨道吊直流母线供电模式 Using 5G technology to realize DC bus power supply mode of track crane in yard
- 大型设备智能监测系统 Intelligent Monitoring System for Large Equipment
- 物联网可视化监控平台 Internet of Things Visual Monitoring Platform
- 冷藏箱插拔电自动化 Automation of reefer plug-in and pull-out

.....





谢谢大家!

Thank You!



IAPH Guangzhou 2019 World
Ports Conference